BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT46568

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/12/2020-21, Date: 22-01-2021

Name of Work:Maintenance of RO Plant in Ward No 10 Doddabommasandra Vidyaranyapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S Narayana Rao ( )	
				In Figures	In Words
1	57.6	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specifications. MORTH Specification No. 202 Page No. 140, Item No. 18.47, PWD SR 2018-19	Cum	838.59	Rupees Eight Hundred Thirty Eight and Fifty Nine Paise Only
2	291.6	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strata by Manual Means . Page No. 07 / Item No.2.22.1 / PRED SR 2019-20 Ordinary Soil	Cum	230.56	Rupees Two Hundred Thirty and Fifty Six Paise Only
3	1080	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.61 item No. 10.01.2 b PRED SR 2019-20.	Rmtr	182.16	Rupees One Hundred Eighty Two and Sixteen Paise Only
4	291.6	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including watering, consolidation in layers of 15 cm thick including disposing of the sunplus earth with a lead of 200 mtrs Page No. 8 / Item No. 2.25 / PRED SR 2019-20	Cum	90.64	Rupees Ninety and Sixty Four Paise Only
5	22	KSRB13-6.3-7 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 65mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3. P. No.92 / I. No. 13.38 PWD SR 2018-19	Each	2401.96	Rupees Two Thousand Four Hundred One and Ninety Six Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
9/02